

Working Groups 14 and 15
Underground Construction and the
Environment and Mechanized Tunnelling

N° ISBN: 978-2-9701242-0-7

ITA REPORT N°21 / APRIL 2019





ITA Report n°21 - Handling, Treatment and Disposal of Tunnel Spoil Materials

N°ISBN: 978-2-9701242-0-7 / APRIL 2019 - Layout: Longrine - Avignon - France - www.longrine.fr

The International Tunnelling and Underground Space Association/Association Internationale des Tunnels et de l'Espace Souterrain (ITA/AITES) publishes this report to, in accordance with its statutes, facilitate the exchange of information, in order: to encourage planning of the subsurface for the benefit of the public, environment and sustainable development to promote advances in planning, design, construction, maintenance and safety of tunnels and underground space, by bringing together information thereon and by studying questions related thereto. This report has been prepared by professionals with expertise within the actual subjects. The opinions and statements are based on sources believed to be reliable and in good faith. However, ITA/AITES accepts no responsibility or liability whatsoever with regard to the material published in this report. This material is: information of a general nature only which is not intended to address the specific circumstances of any particular individual or entity; not necessarily comprehensive, complete, accurate or up to date; This material is not professional or legal advice (if you need specific advice, you should always consult a suitably qualified professional).

HANDLING, TREATMENT AND DISPOSAL OF TUNNEL SPOIL MATERIALS

Working Groups 14 and 15
Underground Construction and the
Environment and Mechanized Tunnelling



Loading of tunnel muck, Rosten HEPP, Norway. (Photo Ø. Fæhn, Skanska Norge AS)

1 INTRODUCTION	6
2 ACKNOWLEDGEMENTS	8
3 SUMMARY AND INTRODUCTION	9
4 OPPORTUNITIES FORTUNNEL SPOIL	10
4.1 Temporary construction purposes	14
4.2 Embankments, landfill and erosion protection	14
4.3 Earth and rock fill dams	15
4.3.1 Førsvatn Earth and Rock Fill Dam, Norway	15
4.3.2 Some Comments to Blasted Tunnel Spoil	16
4.3.3 Studies for Utilizing Crushed Rock as Impervious Core	16
4.4 Tunnel Spoil from TBM Rock Tunnels	18
4.4.1 Typical Strengths of Different Rock Types	23
4.5 Construction Aggregates and Ballast	23
4.5.1 Some Basic Requirements	24
4.6 Tunnel Spoil from Soft Ground TBM Tunnels	25
4.7 Sampling and Testing	26
4.7.1 Some Relevant Tests	27
4.7.2 Procedures for On-Site Testing	27
4.8 Alternative Excavation Methods	29
5 CHALLENGES	31
5.1 Geology and Ground Conditions	31
5.2 Excavation	31
5.3 Logistics, Management, Handling and Transportation of Muck	34
5.4 Temporary Storage and Permanent Deposits	
6 CONTRACTUAL ISSUES	38
7 RECOMMENDATIONS AND CHECK LIST	39
7.1 Recommendations	39
7.1.1 Planning Stage	39
7.1.2 Preparation of Contract Documents	39
7.1.3 Construction	39
7.1.4 Operation and Post Operational Stage	39
7.2 Check Lists	39
7.2.1 Planning Stage	39

7.2.2 Contract	36
7.2.3 Construction Stage	39
7.2.4 Post Construction Stage	39
8 RECEIVED QUESTIONNAIRES AND SELECTED PAPERS	40
8.1 Questionnaires	40
8.2 Selected Case Studies	41
8.2.1 Suhua Highway Improvement Project, Taiwan	41
8.2.2 Caopu Tunnel, Taiwan	44
8.2.3 Northside Storage Tunnel Project, Sydney, Australia	46
8.2.4 Crossrail Project, London, England	49
8.2.5 Le Farette, Romande Energie Hydropower, Switzerland	49
8.2.6 Gotthard Base Tunnel - Materials Management for 15 Years	50
8.2.7 Mechanized Tunnelling with EPB TBMs; Environmental Aspects - Aspects of Soil Conditioning	Process
The Approach in Italy	54
8.2.8 Nobilitation of Tunnelling Waste as Building Material - Issues and Solutions	55
9 REFERENCES	57
10 RFURTHER READINGS MATERIALS	58
11 ENCLOSURES	59
11.1 Questionnaire Format	59
TABLES	
TABLES	
1. Projects Referenced in the Report	7
Example of Actual Projects with EXMAT Quantities	13
3. Rock Material Properties	
3. Hock Material Properties	23
4. Material Tests – Tunnel Spoil	27
7	
5. Rock Hardness Requirements	28
6. Petrographic Requirements	28
7. Handling, Treatment and Disposal Tunnel Muck	AC
T. Harding, Hourront and Diopoda Tarino Madri	
8. Characteristics of Tunnels in the Suhua Highway Improvement Project	41